



	Buildings - For details see Architectural Drawings & Structural Engineers report.
	Reinstate Bandstand - for details see Conservation Architect/ Structural Engineers report and Laings Foundry specialist information from Round 1 Bid.
	Retain Asphalt Surfacing
	Asphalt Surfacing - new construction footpath with 50mm pin kerb edge.
	16mm thick resin bound surfacing (Buff colour) as top coat to existing surface and granite sett edging.
	Red Asphalt Surfacing - At existing paths.
	Red Asphalt Surfacing - New paths.
	Gravel surfacing - 5 - 10mm chippings silver grey.
	Pembroke concrete slab surfacing 80mm thick - 5 size mix silver granite colour
	Proprietary Concrete Setts with Granite Aggregate.
	CEDEC surfacing.
	Whindust path.
	Bonded rubber mulch play surfacing
	Wide top silver grey kerb as step seat
	Flush mid grey conservation granite channel 300mm wide.
	125mm high silver grey conservation kerb steps.
	Timber sleeper edges to planters single height.
	Timber sleeper edges to planters double height.
	Replace existing precast concrete copes to walling with new sawn Yorkstone copes, 125 mm deep.
	Existing trees - for management proposals refer to Tree Management drawing previously issued.
	Proposed trees - 20 - 40 cm girth underground guyed and planted in pits.
	Yew hedge - plant in 600mm prepared trench.
	Salix & Alder planting - (notch planting whips at 3 per m2 allowance for 15% feathered pit planted)
	Living Landscapes wildflower meadow - Standard Wet Meadow mix by Scotia Seeds or approved equivalent at 5g/m2.
	Espalier heritage fruit trees - 20 - 40 cm girth tied in to walls as support.
	2m high timber trellis structure include for climbing roses 3L container grown along full length shown.
	Climbers for north facing walls, allow for 1 no 3L container grown per 4m length.
	Mixed herbaceous border planting along Royal Promenade.
	Mixed grass and perennial planting.
	Shrub planting - allow relocation of existing specimen plants & 40% of area as new 3L pot grown at 3 per m2. Underplanting of roses with snowdrop bulbs mixed varieties at 15 bulbs per m2.
	Rose planting - Underplanted with ground cover.
	Box Hedge.
	Mown grass path
	Gardeners service yard - new asphalt surfacing and 3 no timber fenced storage compounds, 1.8m high.
	New steel vertical post and panel fencing with finials, 1.2m high.
	New Gate.
	Relocate existing bowtop fence to new alignment.
	5m high, Aluminium conical Post-top column c/w Cityspirit lantern, painted to RAL 7043
	Strip back & refurbish existing timber memorial benches.
	New contemporary timber bench seats.
	New timber accessible picnic tables/ benches
	New stainless steel Sheffield style cycle racks
	New timber bollards to restrict access.
	20 New Glasdon steel litter bins.
	SIMBA Sculpture tree retained in existing position.
	Orientation points 6no.
	Saughtonhall interpretation utilising granite & 30 - 35cm girth, pleached hornbeam underground guyed & 3no interpretive signs
	Play equipment to be moved/removed to reestablish Royal Promenade vista.
	9no Aluminium Saughton Park sign on posts
	Fixed chess tables & stool seats (2no)
	6no Beehives within fenced area.
<b>Other Works (Outwith HLF Scheme)</b>	
	Micro Hydro Scheme.
	Underground pipes for Ground Source Heat System.

0 10 25 50 100m

North Point

Project: **Saughton Park**

Client: **City of Edinburgh Council**

Date: **03.2015**

Scale: **1:1000**

Original Size: **A1**

Copyright Acknowledgment: Ordnance Survey © Crown Copyright 2014. All rights reserved. Licence No. AL100017966.

Quality Assurance: UKAS 005 Quality Assurance ISO 9001:2008 SGS Certificate GB02/54539

111 McDonald Road EDINBURGH EH7 4NW Tel: 0131 550 6500 Fax: 0131 557 6723 mail@ironsidefarrar.com

offices also in BELLSHILL & MANCHESTER

Drawing No: **8311\_117** Revision: **F**

Drawing Name and Location: SAUGHTON PARK MASTERPLAN STAGE 3  
 Drawing Title: Saughton Park Masterplan Stage 3  
 Drawing Number: 8311\_117